



QTY 5

CT-1 THRU CT-5 OVERFLOW

Murphy-PFFS-SPOOL-BOM							
Mark	Qty	Description	End 1	End 2	Lft	LDec	Size
6	5	150lb RF Sch 40 Bore SA105 CS WN Flg					4
1	15	Style 177N QuickVic EHP Pnt Flexible Cpl					4
7	5	150lb CS Flange Cap Screw Set					4 (5/8x1-3/4)
3	5	LD-2000 Butterfly Valve					4
2	5	Sch 40 SA-53B CS ERW Pipe PE	Grooved End	BEV	3"	3.000	4
4	10	Sch 40 SA-53B CS ERW Pipe PE	Grooved End	Grooved End	4"	4.000	4
5	5	Sch 40 SA-53B CS ERW Pipe PE	MPT	Grooved End	2'-1"	25.023	4

DRN

JMM

CHK

APP

JOB NO.

210140

REF.DWG.

DRAWING NO./TRACKING NO.

210140-A-UPL3-4D

WUSM RESEARCH BUILDING

NRB

LVLO3 CT SPOOLS

SERVICE NAME

TOWER OVERFLOW

QTY.

5

SHT/NO

1 of 1

REV

0

6/15/2021

QA/QC ACCEPT

FLANGE WEIGHT/ORIENTATION

☐

FITTING ORIENTATION

☐

BOLTS/CPLG'S/TH'D TIGHT

☐

SPOOL IDENTIFICATION

☐

SPEC.

NA

ASME

NA

X-RAY

NA

HYDRO TEST

NA

PWHT

NA

COMMENTS

REV

0

DATE

DESCRIPTION

DRN

CHK

APP

**MURPHY**  
SINCE 1907

CONSTRUCTORS • ENGINEERS  
MECHANICAL • INDUSTRIAL

1233 N. Price Rd.  
St. Louis, MO 63132-2303  
314-997-6600 phone  
BIMCAD@murphy-stl.com